



TEST REPORT

Equipment : Fanless embedded controller.

Model / Type : xxxxAEC-6841-xxxxxxx (Where x is 0-9, A-Z, - or blank) for marketing purpose (rated 9 – 30 V dc)

Serial No. : None

Applicant : Aaeon Technology Inc.
5F,No.135 , Lane 235, Pao Chiao Rd., Hsin Tien City, Taipei, Taiwan, R.O.C.

Tests are done according to IEC standard IEC 60255-27 : 2005 .
Test results are valid only for the tested sample . The report can only be copied in full.
Partial duplication should have the authorization from the test lab.

Samples received : January 19 , 2010

Test date : January 19 , 2010

Name and address of the testing laboratory :

Universal Testing Inc.
2F,No.13,Lane 28,Sec.1,Huanshan Rd., NeiHu, Taipei, Taiwan, R.O.C.

Prepared by : Tony Cheng
Signature

January 20 , 2010
Date

Tony Cheng
Supervisor

Reviewed by : Steven Chang
Signature

January 20 , 2010
Date

Steven Chang
Manager





Clause 10.5.3.2 Dielectric Voltage Test			
Test Voltage : 2500 Vdc			
Test Duration : 1 minute			
Test location	Com port to earthed ground		
Model : xxxxxAEC-6841-xxxxxxxx	Pass		
Result	Pass		

Attachment Photos of Test Configurations



Dielectric Strength Test