

Report NO: 13P0A0005_I

FSP060-DBAE1

of

AEC-6523

Power Electronics Test Report

Summary	<input checked="" type="checkbox"/> Pass			
	<input type="checkbox"/> Fail			
<input type="checkbox"/> Pass with Deviation				
Comment: _____				
Test Result Summary				
	Critical	Major	Minor	Enhancement
Defect Found	0	0	0	0
Defect Unsolved	0	0	0	0

Issue date

06/06/2013

Approval

Tom Lin

Test Engineer

Sean Hsu

Table of Contents

1. Project	3
2. Power Manufacturer	3
3. Team Member	3
4. Test Equipment	3
5. AC Adapter Spec	3
6. Test Item	4
6.1. AC Input Current	4
6.2. MAX Inrush Current	4
6.3. Input Frequency & Voltage	4
6.4. Switching Test	4
6.5. Efficiency	4
6.6. Line Regulation	4
6.7. Load Regulation	4
6.8. Over-Voltage Protection	4
6.9. Over-Circuit Protection	4
6.10. Over-Load Protection	4
6.11. Short Circuit Protect	4
6.12. Line Voltage Surge	5
6.13. Line Voltage Sag	5
6.14. Ripple & Noise	5
6.15. Setup Time	5
6.16. Hold up Time	5
6.17. Rise Time	5
6.18. Turn on Overshoot	5
6.19. Turn off Undershoot	5
6.20. Remote ON/OFF	5
6.21. Power Good Signal	5
6.22. Power On In Low Temperature	5
6.23. Power On In High Temperature	5
6.24. Power Consumption Test With DC Power	5
6.25. Power Consumption Test With AC Adapter	5

1. Project

FSP060-DBAE1 AC-DC Adapter for AEC-6523 BIOS: R0.1 (6523AM01)04/01/2013

2. Power Manufacturer

FSP

3. Team Member

PM : Jackie Huang ; H/W : VC Chang

4. Test Equipment

4.1. PCB : GENE-CV05W2 REV.A1.0

4.2. CPU : Intel Atom N2600 1.6GHz

4.3. Memory : Transcend , DDR3-1333 2GB

4.4. HDD : Toshiba , MK1060GSC 100GB

4.5. AC Adapter : FSP , Model : FSP060-DBAE1 , O/P : 12V/5A , 60Watt

4.6. USB Mouse : Logitech , Model : M-BT85

4.7. USB Keyboard : Logitech , Model : Y-BL49

4.8. LCD Monitor : CHIMEI , Model : 22SH-L

5. AC Adapter Spec

AC Input : 100VAC~240VAC / 47Hz~63Hz

DC Output : 12Vdc Min Load : 0A Full Load : 5A / 60W

6. Test Item

Test Item	Test Condition / Specification		Sanction	
			Measured	Result
6.1. AC Input Current	I/P:115VAC	1.7A	1.26A	PASS
6.2. MAX Inrush Current	I/P:115VAC	A	8.44A	-
	I/P:230VAC	A	9.2A	-
6.3. Input Frequency & Voltage	I/P:90VAC/47HZ	■ON □ OFF	-	PASS
	I/P:90VAC/63HZ	■ON □ OFF	-	PASS
	I/P:264VAC/47HZ	■ON □ OFF	-	PASS
	I/P:264VAC/63HZ	■ON □ OFF	-	PASS
6.4. Switching Test	Switching Time: 0.5 Sec MIN Load / Full Load	@90VAC ■ON □ OFF	-	PASS
	Switching Time: 0.5 Sec MIN Load / Full Load	@115VAC ■ON □ OFF	-	PASS
	Switching Time: 0.5 Sec MIN Load / Full Load	@230VAC ■ON □ OFF	-	PASS
	Switching Time: 0.5 Sec MIN Load / Full Load	@264VAC ■ON □ OFF	-	PASS
6.5. Efficiency	I/P:90VAC O/P:5A	@%Min	84.188%	-
	I/P:115VAC O/P:5A	@85%Min	85.107%	PASS
	I/P:230VAC O/P:5A	@85%Min	86.695%	PASS
	I/P:264VAC O/P:5A	@%Min	86.496%	-
6.6. Line Regulation	I/P:90VAC~264VAC	<±1%	0.25%	PASS
6.7. Load Regulation	I/P:115VAC O/P:MIN~FULL LOAD	<±5%	4.167	PASS
	I/P:230VAC O/P:MIN~FULL LOAD	<±5%	4.00	PASS
6.8. Over-Voltage Protection	I/P:230VAC O/P:MIN LOAD	V1 : 13~18 (MAX)	-	-
6.9. Over-Circuit Protection	O/P: 12V	7.2A(MAX)	6.35A	PASS
6.10. Over-Load Protection	I/P:90VAC O/P:MIN LOAD	144%	125	PASS
	I/P:115VAC O/P:MIN LOAD	144%	126	PASS
	I/P:230VAC O/P:MIN LOAD	144%	124	PASS
	I/P:264VAC O/P:MIN LOAD	144%	126	PASS
6.11. Short Circuit Protect	I/P:115VAC O/P:MIN LOAD	12V&GND Short	-	PASS
	I/P:230VAC O/P:MIN LOAD	12V&GND Short	-	PASS

6.12. Line Voltage Surge	O/P: FULL LOAD	Surge voltage from 132VAC to 147VAC (0.5sec), back to 132VAC	-	PASS
	O/P: FULL LOAD	Surge voltage from 264VAC to 293VAC (0.5sec), back to 264VAC	-	PASS
6.13. Line Voltage Sag	O/P: FULL LOAD	Sag voltage from 108VAC to 80VAC (0.5sec), back to 108VAC	-	PASS
	O/P: FULL LOAD	Sag voltage from 198VAC to 161VAC (0.5sec), back to 198VAC	-	PASS
6.14. Ripple & Noise	I/P:115VAC O/P:FULL LOAD	$\leq 150\text{mv}$	99mv	PASS
	I/P:230VAC O/P:FULL LOAD	$\leq 150\text{mv}$	93mv	PASS
6.15. Setup Time	I/P:115VAC O/P:FULL LOAD	4S(MAX)	865ms	PASS
	I/P:230VAC O/P:FULL LOAD	mS(MAX)	845ms	PASS
6.16. Hold up Time	I/P:115VAC O/P:FULL LOAD	8mS(MIN)	18.8ms	PASS
	I/P:230VAC O/P:FULL LOAD	8mS(MIN)	79.1ms	PASS
6.17. Rise Time	I/P:115VAC O/P:FULL LOAD	mS(MAX)	24.5ms	PASS
	I/P:230VAC O/P:FULL LOAD	mS(MAX)	24.4ms	PASS
6.18. Turn on Overshoot	Turn on overshoot shall not exceed 10% over nominal voltages@ 20 % LOAD		-	PASS
	Turn on overshoot shall not exceed 10% over nominal voltages@ 20 % LOAD		-	PASS
6.19. Turn off Undershoot	Turn off undershoot shall not exceed 10% over nominal voltages		-	PASS
	Turn off undershoot shall not exceed 10% over nominal voltages		-	PASS
6.20. Remote ON/OFF	Simulate TTL signal to test this function		-	-
6.21. Power Good Signal	Shall go high level with a delay of 100~500ms		-	-
6.22. Power On In Low Temperature	I/P:115VAC (-40°C) After 2HR Power On		-	-
6.23. Power On In High Temperature	I/P:115VAC (75°C)After 2HR Power On		-	-
6.24. Power Consumption Test With DC Power	No Run Prime95	I/P:9VDC 0.84A 7.56W		PASS
	Run Prime95	I/P:9VDC 1.07A 9.63W		PASS
	No Run Prime95	I/P:30VDC 0.26A 7.8W		PASS
	Run Prime95	I/P:30VDC 0.34A 10.2W		PASS
6.25. Power Consumption Test With AC Adapter	No Run Prime95	I/P:100VAC 0.21A 10.7W	O/P: 12V/0.6A 7.2W	PASS
	Run Prime95	I/P:100VAC 0.26A 11.9W	O/P: 12V/0.79A 9.48W	PASS