

Report NO: 12P0A0006_I

FSP084-DMAA1 of AEC-6967 Power Electronics Test Report

Summary	<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail <input type="checkbox"/> Pass with Deviation Comment: _____			
Test Result Summary				
	Critical	Major	Minor	Enhancement
Defect Found	0	0	0	0
Defect Unsolved	0	0	0	0

Issue date	Approval	Test Engineer
06/07/2012	Vincent Chen	Sean Hsu

Table of Contents

1. Project	3
2. Power Manufacturer	3
3. Team Member	3
4. Test Equipment	3
5. AC Adapter Spec	3
6. Test Item	4
6.1. AC Input Current	4
6.2. MAX Inrush Current	4
6.3. Input Frequency & Voltage	4
6.4. Switching Test	4
6.5. Efficiency	4
6.6. Line Regulation	4
6.7. Load Regulation	4
6.8. Over-Voltage Protection	4
6.9. Over-Circuit Protection	4
6.10. Over-Load Protection	4
6.11. Short Circuit Protect	4
6.12. Line Voltage Surge	5
6.13. Line Voltage Sag	5
6.14. Ripple & Noise	5
6.15. Setup Time	5
6.16. Hold up Time	5
6.17. Rise Time	5
6.18. Turn on Overshoot	5
6.19. Turn off Undershoot	5
6.20. Remote ON/OFF	5
6.21. Power Good Signal	5
6.22. Power Consumption Test With DC Power	5
6.23. System Power Consumption Test	5

1. Project

FSP084-DMAA1 AC-DC Adapter for AEC-6967 CPU : INTEL Core I7-2610UE 1.5GHz

2. Power Manufacturer

FSP

3. Team Member

PM : Barnabas Chen ; RD : Tommy Taso

4. Test Equipment

4.1. CPU Board : PBA-QM67 REV.A0.3 BIOS Rev : R0.1 6967AM01(03/17/2012)

4.2. HDD : WD WD1600BEVT 160GB

4.3. Memory : Panram DDR3-1333 8GB*2

4.4. LCD Monitor : CHIMEI , Model : A170E2-T08

4.5. Power Supply : FSP , Model : FSP084-DMAA1 , O/P : 12V/7A , 84Watt

4.6. USB Keyboard : Logitech , Model : Y-BL49

4.7. USB Mouse : Logitech , Model : M-BT85

5. AC Adapter Spec

AC Input : 100VAC~240VAC / 47Hz~63Hz

DC Output : 12Vdc Min Load : 0A Full Load : 7A / 84W

6. Test Item

Test Item	Test Condition / Specification		Sanction	
			Measured	Result
6.1. AC Input Current	I/P:115VAC	1.3A	0.998A	PASS
6.2. MAX Inrush Current	I/P:115VAC	A	4.62A	-
	I/P:230VAC	A	6.38A	-
6.3. Input Frequency & Voltage	I/P:90VAC/47HZ	■ON □ OFF	-	PASS
	I/P:90VAC/63HZ	■ON □ OFF	-	PASS
	I/P:264VAC/47HZ	■ON □ OFF	-	PASS
	I/P:264VAC/63HZ	■ON □ OFF	-	PASS
6.4. Switching Test	Switching Time: 0.5 Sec MIN Load / Full Load	@90VAC ■ON □ OFF	-	PASS
	Switching Time: 0.5 Sec MIN Load / Full Load	@115VAC ■ON □ OFF	-	PASS
	Switching Time: 0.5 Sec MIN Load / Full Load	@230VAC ■ON □ OFF	-	PASS
	Switching Time: 0.5 Sec MIN Load / Full Load	@264VAC ■ON □ OFF	-	PASS
6.5. Efficiency	I/P:90VAC O/P:5A	@83%Min	86.27%	PASS
	I/P:115VAC O/P:5A	@83%Min	87.42%	PASS
	I/P:230VAC O/P:5A	@83%Min	87.15%	PASS
	I/P:264VAC O/P:5A	@83%Min	86.70%	PASS
6.6. Line Regulation	I/P:90VAC~264VAC	<%	0.042%	-
6.7. Load Regulation	I/P:115VAC O/P:MIN~FULL LOAD	<%	1.98%	-
	I/P:230VAC O/P:MIN~FULL LOAD	<%	2.042%	-
6.8. Over-Voltage Protection	I/P:230VAC O/P:MIN LOAD	V1 : 17 (MAX)	-	-
6.9. Over-Circuit Protection	O/P: 12V	9.4A(MAX)	8.5A	PASS
6.10. Over-Load Protection	I/P:90VAC O/P:MIN LOAD	135%	124%	PASS
	I/P:115VAC O/P:MIN LOAD	135%	123%	PASS
	I/P:230VAC O/P:MIN LOAD	135%	124%	PASS
	I/P:264VAC O/P:MIN LOAD	135%	125%	PASS
6.11. Short Circuit Protect	I/P:115VAC O/P:MIN LOAD	12V&GND Short	-	PASS
	I/P:230VAC O/P:MIN LOAD	12V&GND Short	-	PASS

6.12. Line Voltage Surge	O/P: FULL LOAD	Surge voltage from 132VAC to 147VAC (0.5sec), back to 132VAC	-	PASS
	O/P: FULL LOAD	Surge voltage from 264VAC to 293VAC (0.5sec), back to 264VAC	-	PASS
6.13. Line Voltage Sag	O/P: FULL LOAD	Sag voltage from 108VAC to 80VAC (0.5sec), back to 108VAC	-	PASS
	O/P: FULL LOAD	Sag voltage from 198VAC to 161VAC (0.5sec), back to 198VAC	-	PASS
6.14. Ripple & Noise	I/P:115VAC O/P:FULL LOAD	$\leq 150\text{mv}$	117.9mv	PASS
	I/P:230VAC O/P:FULL LOAD	$\leq 150\text{mv}$	96.8mv	PASS
6.15. Setup Time	I/P:115VAC O/P:FULL LOAD	3S(MAX)	748ms	PASS
	I/P:230VAC O/P:FULL LOAD	mS(MAX)	525ms	PASS
6.16. Hold up Time	I/P:115VAC O/P:FULL LOAD	20mS(MIN)	34.6ms	PASS
	I/P:230VAC O/P:FULL LOAD	mS(MIN)	88.5ms	PASS
6.17. Rise Time	I/P:115VAC O/P:FULL LOAD	mS(MAX)	4.88ms	PASS
	I/P:230VAC O/P:FULL LOAD	mS(MAX)	5.87ms	PASS
6.18. Turn on Overshoot	Turn on overshoot shall not exceed 10% over nominal voltages@ 20 % LOAD		-	PASS
	Turn on overshoot shall not exceed 10% over nominal voltages@ 20 % LOAD		-	PASS
6.19. Turn off Undershoot	Turn off undershoot shall not exceed 10% over nominal voltages		-	PASS
	Turn off undershoot shall not exceed 10% over nominal voltages		-	PASS
6.20. Remote ON/OFF	Simulate TTL signal to test this function		-	-
6.21. Power Good Signal	Shall go high level with a delay of 100~500ms		-	-
6.22. Power Consumption Test With DC Power	No Run Prime95	I/P:9VDC 1.51A 13.59W		PASS
	Run Prime95	I/P:9VDC 3.46A 31.14W		PASS
	No Run Prime95	I/P:30VDC 0.54A 16.2W		PASS
	Run Prime95	I/P:30VDC 1.02A 30.6W		PASS
6.23. System Power Consumption Test	No Run Prime95	I/P:100VAC 0.27A 19.2W	O/P: 12V/1.46A	PASS
	Run Prime95	I/P:100VAC 0.40A 39.5W	O/P: 12V/3.02A	PASS